FORM-71

EXTRA ITEM RATE LIST -1 (EIRL)

NAME OF WORK:- Providing Waterbody fencing, fencing to vacant land at waste wier, Damaged boundry fencing,walking path and other development work at Doddabommasandra lake ward 10.

Estimated cost : Rs.8743320.00

Amount Put to tender : Rs. 8743318.00 (As per CSR)

Agreement cost : Rs. Rs.9163030.00

SL No	Item No	Description of work	Unit	Total Anticipated /Approximate Quantity	Rate	Amount	Whether the item are alternative to items	Whether the Extra item is included in the sanctioned estimate.	How the extra cost of the item is prepared to be met out	Whether the extra item is included in the schedule of rate of the SR if so reference	Remarks
1	EI-1	Fabrication supplying and erecting M.S. tubular trusses of all spans as per approved drawing & design with prefabricated steel applications using quality material and are durable, reliable and corrosion and abrasion resistant. Welding shall confirm to latest structural welding code. Quality shall be on various parameters like shape, size, design gauge and polish. The entire trusses is anchored in RCC column by using 4 nos of M.S. anchor bolts at each support with 10mm thick Base plate and shoe plate. The work includes cutting, straightening, placing in position of M.S. pipes and welding wherever necessary and applying one coat of redoxide primer coat to all the members including cost of all materials, labour charges, and hire charges of machineries for cutting, welding, grinding and erection equipments, with all lead and lift, transportation, letc., complete as per specification.	Kg	23939.93	123.31	2951977.64	Yes	NO	Out of Overall savings	PWD BC SR 2018-19 KBS page 43 item 7.29	
		Grill Piller 75 X 75 X 6	1023	1.80							
					Total EIRL Amount Rs	**2951977.64**					

Agreement cost in Rs **9163016.0**

EIRL Amount in Rs **2951977.64**

Percentage $\frac{2951977.64}{9163016.0} \times 100 = 32.22\%$

Consultant
(M/s Embedded Civil Engineering Associates.)

Contractor

Assistant Engineer
Lakes BBMP

Assistant Executive Engineer
Lakes BBMP

Executive Engineer
Lakes. BBMP

Embedded Civil Engineering Associates Bangalore

Chief Engineer
Lakes. BBMP